

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID:

Scope:

Date:

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
WOOD, PLASTIC & COMPOSITE									
	ROUGH CARPENTRY								
	FLOOR FRAMING:								
1	Georga Pacific Floor I- Joist 60W/ 11-7/8" @ 19.2" O.C.	SF	28170	10%	30987	\$ 4.52	\$ 14.50	\$ 19.02	\$ 589,217.81
2	Georga Pacific Roof I- Joist 60W/ 11-7/8" @ 19.2" O.C.	SF	9820	10%	10802	\$ 4.52	\$ 14.50	\$ 19.02	\$ 205,400.03
3	2x10 Corridor Floor Joist @ 16" O.C	SF	3430	10%	3773	\$ 4.52	\$ 12.00	\$ 16.52	\$ 62,311.10
4	2x10 Corridor Roof Rafter @ 16" O.C	SF	1090	10%	1199	\$ 4.52	\$ 12.00	\$ 16.52	\$ 19,801.49
	SHEATHING:								
5	1/2" Th Plywood Sheathing @ Exterior Canopy	SF	2325	10%	2558	\$ 1.65	\$ 1.50	\$ 3.15	\$ 8,056.13
6	3/4 T&G Plywood Floor Sheathing	SF	31595	10%	34755	\$ 1.95	\$ 1.75	\$ 3.70	\$ 128,591.65
7	5/8" Th. OSB Sheathing @ Roof	SF	10915	10%	12007	\$ 2.50	\$ 2.65	\$ 5.15	\$ 61,833.48
	WOOD HAND RAIL:								
8	Handrail Wall Mounted	LF	155	10%	171	\$ 2.50	\$ 5.50	\$ 8.00	\$ 1,364.00
9	Handrail Floor Mounted	LF	150	10%	165	\$ 2.50	\$ 5.50	\$ 8.00	\$ 1,320.00
	WOOD STAIR:								
10	10"W X 4'3"L Wood Stair Tread	EA	53	0%	53	\$ 30.00	\$ 50.00	\$ 80.00	\$ 4,240.00
11	7"W X 4'3"L Wood Stair Riser	EA	59	0%	59	\$ 22.00	\$ 27.00	\$ 49.00	\$ 2,891.00
12	Stringers	LF	575	10%	633	\$ 4.25	\$ 6.60	\$ 10.85	\$ 6,862.63
13	Wood Stair landing w/ framing	SF	250	10%	275	\$ 4.50	\$ 8.50	\$ 13.00	\$ 3,575.00
	WOOD BLOCKING:								
14	Rim Board @ Floor Framing	LF	2905	10%	3196	\$ 4.52	\$ 12.00	\$ 16.52	\$ 52,773.68
	BEAMS/ Headers								
15	2x12x16'L Header @ Opening	LF	2480	10%	2728	\$ 4.20	\$ 7.20	\$ 11.40	\$ 31,099.20
16	1-3/4"x18" MICROLLAMS	LF	115	10%	127	\$ 6.00	\$ 18.53	\$ 24.53	\$ 3,103.05
17	1-3/4"x11-7/8" ML	LF	655	10%	721	\$ 4.20	\$ 11.80	\$ 16.00	\$ 11,528.00
18	1-3/4"x14" ML	LF	225	10%	248	\$ 5.20	\$ 15.23	\$ 20.43	\$ 5,056.43
19	1-3/4"x11-7/8" GL	LF	6	10%	7	\$ 4.20	\$ 13.90	\$ 18.10	\$ 119.46

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
20	1-3/4"x11-7/8" 1.9E MICROLLAMS	LF	685	10%	754	\$ 4.20	\$ 11.80	\$ 16.00	\$ 12,056.00
21	1-3/4"x11-7/8" MICROLLAMS	LF	8	10%	9	\$ 4.20	\$ 11.80	\$ 16.00	\$ 140.80
	FINISH CARPENTRY								
	COUNTERTOP & BACKSPLASH:								
22	Back Splash @ Bath	LF	665	10%	732	\$ 2.95	\$ 15.00	\$ 17.95	\$ 13,130.43
23	Countertop @ Bath	SF	685	10%	754	\$ 23.00	\$ 55.00	\$ 78.00	\$ 58,773.00
	TRIMS @ OPENING:								
24	Aluminum door trim	LF	310	10%	341	\$ 2.20	\$ 2.50	\$ 4.70	\$ 1,602.70
25	Solid wood door trim	LF	7110	10%	7821	\$ 1.80	\$ 6.00	\$ 7.80	\$ 61,003.80
26	Hollow Metal door trim	LF	175	10%	193	\$ 2.20	\$ 2.50	\$ 4.70	\$ 904.75
SUBTOTAL									\$ 1,346,756
OVERHEAD AND PROFIT								7%	\$ 94,273
INSURANCE								3%	\$ 40,403
CONTINGENCY								3%	\$ 40,403
TAX								5%	\$ 67,338
TOTAL TRADE COST									\$ 1,589,172